356 SOP FINISHED FLOORS INSTALLATION



- 1. Place the forward main floor in position (Located between the forward and starboard main bunks).
- 2. Place the port V-berth floor in position (Located in V-berth area).
- 3. Place the starboard V-berth floor in position (Located in V-berth area).
- 4. Place the port main cabin center floor in position (Located aft port side of forward main floor).
- 5. Place the port main cabin aft floor in position (Located aft port side of center main floor).
- 6. Place the chart locker floor in position (Located on top of chart locker step).
- 7. Place the starboard fwd main cabin floor in position (Located aft of starboard bunk).
- 8. Place the fwd mast post bilge floor in position (Located fwd of the mast post).
- 9. Place the aft mast post bilge floor in position (Located aft of the mast post).
- 10. Place the starboard aft main cabin floor in position (Located aft of starboard main cabin floor).
- 11. Place the forward main bilge cover in position (Located aft of aft mast pole floor). This will not be secured.
- 12. Place the center main bilge cover in position (Located aft of forward main bilge cover). This will not be secured.
- 13. Place the aft main bilge floor in position (Located aft of center main bilge cover).
- 14. Place the forward galley floor in position (Located in galley area).
- 15. Place the aft galley floor in position (Located aft of forward galley floor).
- 16. Place the aft stateroom floor in position (Located in aft state room or Q-Berth area).
- 17. Place the forward main cover in position (Located in the main cabin fwd floor). This will not be secured.
- 18. Place the aft bilge cover in position (Located aft of aft main bilge floor). This will not be secured.
- 19. Place the aft galley bilge cover in position (Located in the aft galley floor). This will not be secured.
- 20. All floors that are not going to be secured should have a 1/16" gap all around so they can be lifted out when needed.
- 21. All floors should fit properly and adjustments made from outer edges of outboard floors before securing finished floors to the sub-floors.
- 22. Do not drill into the holly strips. Use a C-7 drill assembly and designated fasteners, secure the appropriate floors in the designated places.

Revision Dates: Expected Time: 4 hrs. Page

